

## Αναρτώμενα ΤΥΛΙΧΤΙΚΑ Τετράγωνης μπάλας

### *Mounted square bale wrappers*

|   |  |  |
|---|--|--|
| ΤΥΠΟΣ   | <u>SW 1114</u>   |  |
| Weight approx. (kg)                                 | 955  |  |
| Bale dimension square (Width x Height x Length) (m) | 0.80 x (0.60-0.90) x 1.80                              |  |
| Bale dimension round (Width x diameter) (m)         | (1.20 x 1.50) x (1.00 x 1.50)                          |  |
| Max bale weight (kg)                                | 1200   |  |
| 1 x pre-stretcher 750mm film                        | As standard  |  |
| Control type  | Manual 2 lever/cable controlled or computer controlled |  |
| Loading system                                      | External   |  |
| Wrapping table                                      | 2 pairs of steel rollers                               |  |

## Συρόμενα ΤΥΛΙΧΤΙΚΑ Τετράγωνης μπάλας

### *Trailed square bale wrappers*

| Specifications                                      | <u>SW 1614</u>                | <u>SW 4014</u>                             |
|---|-------------------------------|--|
| Length (m)  | -                             | 4.7  |
| Transport width (m)                                 | -                             | 2.5  |
| Weight approx. (kg)                                 | -                             | 2820                                       |
| Bale dimension square (Width x Height x Length) (m) | 0.80 x (0.60-0.90) x 1.80     | 80 x (50-100) x 200 & 120 x (60-130) x 200 |
| Bale dimension round (Width x diameter) (m)         | (1.20 x 1.50) x (1.00 x 1.50) | (1.20-1.50) x (90-1.40)                    |
| Max bale weight (kg)                                | 800/1000                      | 1500                                       |
| Oil consumption (l/min)                             | 26                            | 40 to 60 l/min at 150-210 bar              |
| Cable control                                       | Standard                      | -  |
| Computer control                                    | Optional                      | -  |
| Remote control                                      | Optional                      | -  |
| 1 x pre-stretcher 750mm film                        | Standard                      | -  |
| Automatic loading function (Autoload)               | -                             | As standard                                |
| ISOBUS control with IntelliWrap™                    | -                             | As standard                                |